सत्यमेव जयते

File No: SIA/MH/INFRA2/505602/2025

Government of India

Ministry of Environment, Forest and Climate Change

(Issued by the State Environment Impact Assessment Authority(SEIAA), MAHARASHTRA)

***

Dated **15/07/2025**

To,

Manohar Hariram Manchandya
MOHAN LIFESPACES LLP
Ground Floor, Mohan Plaza, next to Mohan Pride, Wayle Nagar, Khadakpada, Kalyan West, Thane - 421301., Kalyan, THANE, MAHARASHTRA, 421301
mohanhomes@gmail.com

Subject: Grant of EC under the provision of the EIA Notification 2006-regarding.

Sir/Madam,

This is in reference to your application for Grant of EC under the provision of the EIA Notification 2006-regarding in respect of project Proposed Residential cum Commercial Project at Plot bearing S. No. 15 Hissa No. 5, Hissa No. 6/1 (PT), 6/2 (PT), S. No. 23, Hissa No. 1 (PT), 2/1 (PT), 2/2 (PT), S. No. 62, Hissa No. 1, 2, 2/1 (PT), Village – Gandhare, Taluka – Kalyan, Dist. – Thane by M/s. Mohan Lifespaces LLP. submitted to Ministry vide proposal number SIA/MH/INFRA2/505602/2025 dated 11/02/2025.

2. The particulars of the proposal are as below :

(i) EC Identification No.	EC24C3801MH5853346N
(ii) File No.	SIA/MH/INFRA2/505602/2025
(iii) Clearance Type	EC
(iv) Category	B2
(v) Project/Activity Included Schedule No.	8(a) Building / Construction
(vii) Name of Project	Proposed Residential cum Commercial Project at Plot bearing S. No. 15 Hissa No. 5, Hissa No. 6/1 (PT), 6/2 (PT), S. No. 23, Hissa No. 1 (PT), 2/1 (PT), 2/2 (PT), S. No. 62, Hissa No. 1, 2, 2/1 (PT), Village – Gandhare, Taluka – Kalyan, Dist. – Thane by M/s. Mohan Lifespaces LLP.
(viii) Name of Company/Organization	MOHAN LIFESPACES LLP
(ix) Location of Project (District, State)	THANE, MAHARASHTRA
(x) Issuing Authority	SEIAA
(xi) Applicability of General Conditions	no
(xiii) Applicability of Specific Conditions	no

3. In view of the particulars given in the Para 1 above, the project proposal interalia including Form-1(Part A and B) were submitted to the Ministry for an appraisal by the State Environment Impact AssessmentAuthority(SEIAA) Appraisal Committee (SEIAA) in the Ministry under the provision of EIA notification 2006 and its subsequent amendments.

4. The above-mentioned proposal has been considered by State Environment Impact AssessmentAuthority(SEIAA) Appraisal Committee of SEIAA in the meeting held on 29/05/2025. The minutes of the meeting and all the Application and documents submitted [(viz. Form-1 Part A, Part B, Part C EIA, EMP)] are available on PARIVESH portal which can be accessed by scanning the QR Code above.

5. The brief about configuration of plant/equipment, products and byproducts and salient features of the project along with environment settings, as submitted by the Project proponent in Form-1 (Part A, B and C)/EIA & EMP Reports/presented during SEIAA are annexed to this EC as Annexure (1).

6. The SEIAA, in its meeting held on 29/05/2025, based on information & clarifications provided by the project proponent and after detailed deliberations recommended the proposal for grant of EC under the provision of EIA Notification, 2006 and as amended thereof subject to stipulation of specific and general conditions as detailed in Annexure (2).

7. The SEIAA has examined the proposal in accordance with the Environment Impact Assessment (EIA) Notification, 2006 & further amendments thereto and after accepting the recommendations of the State Environment Impact AssessmentAuthority(SEIAA) Appraisal Committee hereby decided to grant EC for instant proposal of M/s. Manohar Hariram Manchandya under the provisions of EIA Notification, 2006 and as amended thereof.

8. The Ministry reserves the right to stipulate additional conditions, if found necessary.

9. The EC to the aforementioned project is under provisions of EIA Notification, 2006. It does not tantamount to approvals/consent/permissions etc. required to be obtained under any other Act/Rule/regulation. The Project Proponent is under obligation to obtain approvals /clearances under any other Acts/ Regulations or Statutes, as applicable, to the project.

10. This issues with the approval of the Competent Authority.

Annexure 1

Specific EC Conditions for (Building / Construction)

1. Specific Condition

<table>
<tr><th>S. No</th><th>EC Conditions</th></tr>
<tr><td>1.1</td><td>
<table>
<tr><th>Sr. No.</th><th>Conditions</th></tr>
<tr><td>1.</td><td>PP to obtain IOD/IOA/Concession Document/Plan Approval or any other form of documents as applicable clarifying its conformity with local planning rules and provisions as per the Circular dated 30.01.2014 issued by the Environment Department, Govt. of Maharashtra showing all required RG area as per prevailing Hon’ble Supreme Court Order.</td></tr>
<tr><td>2.</td><td>PP to submit an undertaking signed by PP, Consultant and architect certifying that there is no violation of requirement of EIA notification 2006, amended from time to time</td></tr>
<tr><td>3.</td><td>PP to obtain (i) Solid Waste/C & D Waste Management NOC (ii) Water NOC. The planning authority shall not issue occupation certificate unless all NOCs are obtained by the PP.</td></tr>
<tr><td>4.</td><td>PP to submit concrete plan for disposal/reuse of STP excess treated water.</td></tr>
</table>
</td></tr>
</table>

S. No	EC Conditions
	5. PP to complete tree plantation within the site during construction phase. 6. PP to dispose all e-waste as per E-Waste Management Rules, 2016 and 2022 amended from time to time

Annexure 2

Details of Products & By-products

Name of the product /By-product	Product / By-product	Quantity	Unit	Mode of Transport / Transmission	Remarks (eg. CAS number)
Residential cum commercial building	Residential cum commercial building	98440.88	Sq.mt.	NA	

STATE LEVEL ENVIRONMENT IMPACT ASSESSMENT AUTHORITY

No. SIA/MH/INFRA2/505602/2025
Environment & Climate
Change Department
Room No. 217, 2nd Floor,
Mantralaya, Mumbai- 400032.

To
M/s. Mohan Lifespaces LLP,
S. No. 15 Hissa No. 5, Hissa No. 6/1 (PT), 6/2 (PT),
S. No. 23, Hissa No. 1 (PT), 2/1 (PT), 2/2 (PT),
S. No. 62, Hissa No. 1, 2, 2/1 (PT), Village – Gandhare,
Taluka – Kalyan, Dist. – Thane.

Subject : Environmental Clearance for Proposed Residential cum Commercial Project at Plot bearing S. No. 15 Hissa No. 5, Hissa No. 6/1 (PT), 6/2 (PT), S. No. 23, Hissa No. 1 (PT), 2/1 (PT), 2/2 (PT), S. No. 62, Hissa No. 1, 2, 2/1 (PT), Village – Gandhare, Taluka – Kalyan, Dist. – Thane by M/s. Mohan Lifespaces LLP.

Reference : Application no. SIA/MH/INFRA2/505602/2025

This has reference to your communication on the above-mentioned subject. The proposal was considered by the SEAC-2 in its 239th meeting under screening category 8 (a) B2 as per EIA Notification, 2006 and recommend to SEIAA. Proposal then considered in 294th (Day-2) meeting of State Level Environment Impact Assessment Authority (SEIAA) held on 29th May, 2025.

2. Brief Information of the project submitted by you is as below:-

Sr. No.	Description	Details	
1	Whether the project falls within 5km of any protected area notified under Wildlife (Protection) Act, 1972, Critically Polluted Areas and Severely Polluted Areas as identified by the CPCB, eco- sensitive areas notified under Section 3(2) of Environment (Protection) Act,1896 as per Hon'ble National Green Tribunal order dated 9th August 2024	No	
2	Proposal Number	**SIA/MH/INFRA2/505602/2024**	
3	Name of Project	Residential cum Commercial Project at Plot bearing S. No. 15 Hissa No. 5, Hissa No. 6/1 (PT), 6/2 (PT), S. No. 23, Hissa No. 1 (PT), 2/1 (PT), 2/2 (PT), S. No. 62, Hissa No. 1, 2, 2/1 (PT), Village – Gandhare, Taluka – Kalyan, Dist. – Thane by M/s. Mohan Lifespaces LLP.	
4	Project category	8a (B2)	
5	Type of Institution	Others	
	Project Proponent	Name	Mr. Manohar Hariram Manchandya

<table>
<tr><td rowspan="3">6</td><td rowspan="3"></td><td>Regd. Office address</td><td>G1, Mohan Plaza Next to Mohan pride, Waylen agar, Khadakpada kalyan-421301.</td></tr>
<tr><td>Contact number</td><td>9769582166 / 0251-2305999</td></tr>
<tr><td>E-mail</td><td>mohanhomes@gmail.com</td></tr>
<tr><td>7</td><td>Consultant</td><td colspan="2">EIA Coordinator: Mr. Sourabh Jaiswar
Pollution and Ecology Control Services, NABET /EIA/2225/RA 0291 valid upto 16-10-2025.</td></tr>
<tr><td>8</td><td>Applied for</td><td colspan="2">New Project</td></tr>
<tr><td>9</td><td>Location of the project</td><td colspan="2">Plot bearing S. No. 15 Hissa No. 5, Hissa No. 6/1 (PT), 6/2 (PT), S. No. 23, Hissa No. 1 (PT), 2/1 (PT), 2/2 (PT), S. No. 62, Hissa No. 1, 2, 2/1 (PT), Village – Gandhare, Taluka – Kalyan, Dist. – Thane.</td></tr>
<tr><td>10</td><td>Latitude and Longitude</td><td colspan="2">Latitude: 73° 8'20.75"E, Longitude: 73° 8'20.75"E</td></tr>
<tr><td>11</td><td>Plot Area (sq.m.)</td><td colspan="2">13774.00 sq.mt.</td></tr>
<tr><td>12</td><td>Area handed over to KDMC (sq.m.)</td><td colspan="2">9641.80 sq.mt</td></tr>
<tr><td>13</td><td>Balance Plot area (sq.m.)</td><td colspan="2">4132.20 sq.mt</td></tr>
<tr><td>14</td><td>Ground coverage (m^2) & %</td><td colspan="2">2526.85 sq.mt (48.30%)</td></tr>
<tr><td>15</td><td>FSI Area (sq.m.)</td><td colspan="2">60764.17 sq.mt</td></tr>
<tr><td>16</td><td>Non-FSI (sq.m.)</td><td colspan="2">37,676.71 sq.mt</td></tr>
<tr><td>17</td><td>Proposed built-up area (FSI +Non FSI) (sq.m.)</td><td colspan="2">98,440.88 sq.mt</td></tr>
<tr><td>18</td><td>TBUA (m^2) approved by Planning Authority till date</td><td colspan="2">98,440.88 sq.mt vide LOI dated 24.02.2025</td></tr>
<tr><td>19</td><td>Earlier EC details with Total Construction area, if any.</td><td colspan="2">NA</td></tr>
<tr><td>20</td><td>Construction completed as per earlier EC (FSI + Non FSI) (sq.m.)</td><td colspan="2">NA</td></tr>
<tr><td></td><td>Previous EC / Existing Building</td><td colspan="2">Proposed Configuration</td></tr>
<tr><td>21</td><td>NA</td><td colspan="2"><table><tr><th>Name</th><th>Configuration</th><th>Height</th></tr><tr><td>Bldg.</td><td>Gr./St/Comm.+1st To 9th Level Podium+10th (Amenity) +11th (Service Fl.) +12th To 59th Residential Floors.</td><td>206 .80 m</td></tr></table></td></tr>
<tr><td>22</td><td>No of Tenements &Shop</td><td colspan="2">Flats 188 Nos; Shops 21 Nos.</td></tr>
<tr><td>23</td><td>Total Population</td><td colspan="2">2606 nos.</td></tr>
<tr><td>24</td><td>Total Water Requirements CMD</td><td colspan="2">181 KLD</td></tr>
<tr><td>25</td><td>Under Ground Tank (UGT) location</td><td colspan="2">Below Ground</td></tr>
<tr><td>26</td><td>Source of water</td><td colspan="2">KDMC and Recycled Water.</td></tr>
<tr><td>27</td><td>STP Capacity & Technology</td><td colspan="2">175 KLD & MBBR Technology</td></tr>
<tr><td>28</td><td>STP Location</td><td colspan="2">Below Ground</td></tr>
<tr><td>29</td><td>Sewage Generation CMD & % of sewage discharge in sewer line</td><td colspan="2">157 KLD & 32.00% of sewage discharge in sewer line.</td></tr>
<tr><td rowspan="3">30</td><td rowspan="3">Solid Waste Management during Construction Phase</td><td>Type</td><td>Quantity (Kg/d)</td><td>Treatment / Disposal</td></tr>
<tr><td>Dry waste</td><td>10</td><td>Local recyclers</td></tr>
<tr><td>Wet waste</td><td>15</td><td>Local recyclers</td></tr>
<tr><td>31</td><td>Total Solid Waste Quantities with type during Operation Phase &</td><td>Type</td><td>Quantity (Kg/d)</td><td>Treatment /disposal</td></tr>
</table>

	Capacity of OWC to be installed	Dry waste	359	Disposed-off through authorized recyclers
		Wet waste	239	Treated in OWC
		E-Waste	5	Authorize vendor
		STP Sludge	20	Used as Manure.
32	R.G. Area in sq.m.	RG required – Nil as the plot is Garden Reservation Plot under Accommodation & Reservation scheme		
		RG provided on Mother earth/Ground – Nil		
		Total – Nil		
		Existing trees on plot: 189 Nos.		
		Number of trees to be planted: 140 nos.		
		In RG area/ along Plot Boundary: 140 nos.		
		Miyawaki Plantation: Nil.		
		a) Number of trees to be cut: 26 Nos.		
		Number of trees to be retained: 163 Nos.		
		Total No. of Trees: 303 Nos.		
33	Power requirement	During Construction Phase: 100 KW During Operation Phase: 3567 KW		
34	Energy Efficiency	a) Total Energy saving (%): 21.65 % b) Solar energy (%): 5.00%		
35	D.G. set capacity	Nil as Alternate Current is proposed.		
36	Parking	4-Wheeler: 559 nos; 2-Wheeler: 1026 nos.		
37	No. & capacity of Rain water harvesting tanks /Pits	RWH Capacity 93 cum & 98 cum		
38	Project Cost in (Cr.)	370 Cr.		
39	EMP Cost	Particulars	Capital Cost in Cr.	O & M Cost in Lakhs.
		Construction Phase	0.18	8.98
		Operation Phase	2.96	18.50
40	CER Details with justification if any....as per MoEF&CC circular dated 01/05/2018	NA		
41	Details of Court Cases/litigations w.r.t the project and project location, if any.	None		

3. Proposal was considered by SEIAA in its 294th (Day-2) meeting held on 29th May, 2025 and decided to accord Environment Clearance to the said project under the provisions of Environment Impact Assessment Notification, 2006 subject to implantation of following terms and conditions-

Specific Conditions:

A. SEAC Conditions-

1. PP to obtain IOD/IOA/Concession Document/Plan Approval or any other form of documents as applicable clarifying its conformity with local planning rules and provisions as per the Circular dated 30.01.2014 issued by the Environment Department, Govt. of Maharashtra showing all required RG area as per prevailing

Hon'ble Supreme Court Order.

2. PP to submit an undertaking signed by PP, Consultant and architect certifying that there is no violation of requirement of EIA notification 2006, amended from time to time
3. PP to obtain (i) Solid Waste/C & D Waste Management NOC (ii) Water NOC. The planning authority shall not issue occupation certificate unless all NOCs are obtained by the PP.
4. PP to submit concrete plan for disposal/reuse of STP excess treated water.
5. PP to complete tree plantation within the site during construction phase.
6. PP to dispose all e-waste as per E-Waste Management Rules, 2016 and 2022 amended from time to time

B. SEIAA Conditions-

1. PP submitted that, the proposed plot is Garden Reservation under Accommodation & Reservation scheme Chapter 11, Rule No. 11.1, Table 11-A (1.1). The plot is under Garden reservation as per DP plan of KDMC. Mandatory RG is not applicable to their project as per the provisions of UDCPR 2020. Local planning authority to ensure the validity of the same.
2. PP to keep open space unpaved so as to ensure permeability of water. However, whenever paving is deemed necessary, PP to provide grass pavers of suitable types & strength to increase the water permeable area as well as to allow effective fire tender movement.
3. PP to achieve at least 5% of total energy requirement from solar/other renewable sources.
4. PP Shall comply with Standard EC conditions mentioned in the Office Memorandum issued by MoEF& CC vide F.No.22-34/2018-IA.III dt.04.01.2019.
5. SEIAA decided to grant EC for FSI-60764.17 m2, Non FSI- 37,676.71 m2 and total BUA- 98,440.88 m2. (Plan approval No. LOI-KDMC/NRV/5170 dated.24.02.2025)

General Conditions:

a) Construction Phase :-

I. The solid waste generated should be properly collected and segregated. Dry/inert solid waste should be disposed of to the approved sites for land filling after recovering recyclable material.

II. Disposal of muck, Construction spoils, including bituminous material during construction phase should not create any adverse effect on the neighbouring communities and be disposed taking the necessary precautions for general safety and health aspects of people, only in the approved sites with the approval of competent authority.

III. Any hazardous waste generated during construction phase should be disposed of as per applicable rules and norms with necessary approvals of the Maharashtra Pollution Control Board.

IV. Adequate drinking water and sanitary facilities should be provided for construction workers at the site. Provision should be made for mobile toilets. The safe disposal of wastewater and solid wastes generated during the construction phase should be ensured.

V. Arrangement shall be made that waste water and storm water do not get mixed.

VI. Water demand during construction should be reduced by use of pre-mixed concrete, curing agents and other best practices.

VII. The ground water level and its quality should be monitored regularly in consultation with Ground Water Authority.

VIII. Permission to draw ground water for construction of basement if any shall be obtained from the competent Authority prior to construction/operation of the project.

IX. Fixtures for showers, toilet flushing and drinking should be of low flow either by use of aerators or pressure reducing devices or sensor based control.

X. The Energy Conservation Building code shall be strictly adhered to.

XI. All the topsoil excavated during construction activities should be stored for use in horticulture / landscape development within the project site.

XII. Additional soil for levelling of the proposed site shall be generated within the sites (to the extent possible) so that natural drainage system of the area is protected and improved.

XIII. Soil and ground water samples will be tested to ascertain that there is no threat to ground water quality by leaching of heavy metals and other toxic contaminants.

XIV. PP to strictly adhere to all the conditions mentioned in Maharashtra (Urban Areas) Protection and Preservation of Trees Act, 1975 as amended during the validity of Environment Clearance.

XV. The diesel generator sets to be used during construction phase should be low sulphur diesel type and should conform to Environments (Protection) Rules prescribed for air and noise emission standards.

XVI. Vehicles hired for transportation of Raw material shall strictly comply the emission norms prescribed by Ministry of Road Transport & Highways Department. The vehicle shall be adequately covered to avoid spillage/leakages.

XVII. Ambient noise levels should conform to residential standards both during day and night. Incremental pollution loads on the ambient air and noise quality should be closely monitored during construction phase. Adequate measures should be made to reduce ambient air and noise level during construction phase, so as to conform to the stipulated standards by CPCB/MPCB.

XVIII. Diesel power generating sets proposed as source of backup power for elevators and common area illumination during construction phase should be of enclosed type and conform to rules made under the Environment (Protection) Act, 1986. The height of stack of DG sets should be equal to the height needed for the combined capacity of all proposed DG sets. Use low sulphur diesel is preferred. The location of the DG sets may be decided with in consultation with Maharashtra Pollution Control Board.

XIX. Regular supervision of the above and other measures for monitoring should be in place all through the construction phase, so as to avoid disturbance to the surroundings by a separate environment cell /designated person.

B) Operation phase:-

I. a) The solid waste generated should be properly collected and segregated. b) Wet waste should be treated by Organic Waste Converter and treated waste (manure) should be utilized in the existing premises for gardening. And, no wet garbage will be disposed outside the premises. c) Dry/inert solid waste should be disposed of to the approved sites for land filling after recovering recyclable material.

II. E-waste shall be disposed through Authorized vendor as per E-waste (Management and Handling) Rules, 2016.

III. a) The installation of the Sewage Treatment Plant (STP) should be certified by an independent expert and a report in this regard should be submitted to the MPCB and Environment department before the project is commissioned for operation. Treated effluent emanating from STP shall be recycled/ reused to the maximum extent possible. Treatment of 100% grey water by decentralized treatment should be done. Necessary measures should be made to mitigate the odour problem from STP. b) PP to give100 % treatment to sewage /Liquid waste and explore the possibility to recycle at least 50 % of water, Local authority should ensure this.

IV. Project proponent shall ensure completion of STP, MSW disposal facility, green belt development prior to occupation of the buildings. As agreed during the SEIAA meeting, PP to explore possibility of utilizing excess treated water in the adjacent area for gardening before discharging it into sewer line No physical occupation or allotment will be given unless all above said environmental infrastructure is installed and made functional including water requirement.

V. The Occupancy Certificate shall be issued by the Local Planning Authority to the project only after ensuring sustained availability of drinking water, connectivity of sewer line to the project site and proper disposal of treated water as per environmental norms.

VI. Traffic congestion near the entry and exit points from the roads adjoining the proposed project site must be avoided. Parking should be fully internalized and no public space should be utilized.

VII. PP to provide adequate electric charging points for electric vehicles (EVs).

VIII. Green Belt Development shall be carried out considering CPCB guidelines including selection of plant species and in consultation with the local DFO/ Agriculture Dept.

IX. A separate environment management cell with qualified staff shall be set up for implementation of the stipulated environmental safeguards.

X. Separate funds shall be allocated for implementation of environmental protection measures/EMP along with item-wise breaks-up. These cost shall be included as part of the project cost. The funds earmarked for the environment protection measures shall not be diverted for other purposes.

XI. The project management shall advertise at least in two local newspapers widely circulated in the region around the project, one of which shall be in the Marathi language of the local concerned within seven days of issue of this letter, informing that the project has been accorded environmental clearance and copies of clearance letter are available with the Maharashtra Pollution Control Board and may also be seen at Website at parivesh.nic.in

XII. A copy of the clearance letter shall be sent by proponent to the concerned Municipal Corporation and the local NGO, if any, from whom suggestions/representations, if any, were received while processing the proposal. The clearance letter shall also be put on the website of the Company by the proponent.

XIII. The proponent shall upload the status of compliance of the stipulated EC conditions, including results of monitored data on their website and shall update the same periodically. It shall simultaneously be sent to the Regional Office of MoEF, the respective Zonal Office of CPCB and the SPCB. The criteria pollutant levels namely;

SPM, RSPM. SO2, NOx (ambient levels as well as stack emissions) or critical sector parameters, indicated for the project shall be monitored and displayed at a convenient location near the main gate of the company in the public domain.

C) General EC Conditions:-

I. PP has to strictly abide by the conditions stipulated by SEAC& SEIAA.

II. If applicable Consent for Establishment" shall be obtained from Maharashtra Pollution Control Board under Air and Water Act and a copy shall be submitted to the Environment department before start of any construction work at the site.

III. Under the provisions of Environment (Protection) Act, 1986, legal action shall be initiated against the project proponent if it was found that construction of the project has been started without obtaining environmental clearance.

IV. The project proponent shall also submit six monthly reports on the status of compliance of the stipulated EC conditions including results of monitored data (both in hard copies as well as by e-mail) to the respective Regional Office of MoEF, the respective Zonal Office of CPCB and the SPCB.

V. The environmental statement for each financial year ending 31st March in Form-V as is mandated to be submitted by the project proponent to the concerned State Pollution Control Board as prescribed under the Environment (Protection) Rules, 1986, as amended subsequently, shall also be put on the website of the company along with the status of compliance of EC conditions and shall also be sent to the respective Regional Offices of MoEF by e-mail.

VI. No further Expansion or modifications, other than mentioned in the EIA Notification, 2006 and its amendments, shall be carried out without prior approval of the SEIAA. In case of deviations or alterations in the project proposal from those submitted to SEIAA for clearance, a fresh reference shall be made to the SEIAA as applicable to assess the adequacy of conditions imposed and to add additional environmental protection measures required, if any.

VII. This environmental clearance is issued subject to obtaining NOC from Forestry & Wild life angle including clearance from the standing committee of the National Board for Wild life as if applicable & this environment clearance does not necessarily implies that Forestry & Wild life clearance granted to the project which will be considered separately on merit.

4. The environmental clearance is being issued without prejudice to the action initiated under EP Act or any court case pending in the court of law and it does not mean that project proponent has not violated any environmental laws in the past and whatever decision under EP Act or of the Hon'ble court will be binding on the project proponent. Hence this clearance does not give immunity to the project proponent in the case filed against him, if any or action initiated under EP Act.

5. This Environment Clearance is issued purely from an environment point of view without prejudice to any court cases and all other applicable permissions/ NOCs shall be obtained before starting proposed work at site.

6. In case of submission of false document and non-compliance of stipulated conditions, Authority/ Environment Department will revoke or suspend the Environment clearance without any intimation and initiate appropriate legal action under Environmental Protection Act, 1986.

7. Validity of Environment Clearance: The environmental clearance accorded shall be valid

as per EIA Notification, 2006, amended from time to time.

8. The above stipulations would be enforced among others under the Water (Prevention and Control of Pollution) Act, 1974, the Air (Prevention and Control of Pollution) Act, 1981, the Environment (Protection) Act, 1986 and rules there under, Hazardous Wastes (Management and Handling) Rules, 1989 and its amendments, the public Liability Insurance Act, 1991 and its amendments.

9. Any appeal against this Environment clearance shall lie with the National Green Tribunal (Western Zone Bench, Pune), New Administrative Building, 1st Floor, D-Wing, Opposite Council Hall, Pune, if preferred, within 30 days as prescribed under Section 16 of the National Green Tribunal Act, 2010.

Jayashree Bhoj
(Member Secretary, SEIAA)

Copy to:

1. Chairman, SEIAA, Mumbai.
2. Secretary, MoEF & CC, IA- Division MOEF & CC
3. Member Secretary, Maharashtra Pollution Control Board, Mumbai.
4. Regional Office MoEF & CC, Nagpur
5. District Collector, Thane.
6. Commissioner, Kalyan Dombivali Municipal Corporation
7. Regional Officer, Maharashtra Pollution Control Board, Kalyan.

Signed by
Jayashree Shrikant Bhoj
Date: 15-07-2025 16:12:26
Reason: Verified and signed